

**PUMP STATION NO. 23 MODIFICATIONS  
SUSSEX COUNTY CONTRACT NO. 14-22  
SUSSEX COUNTY, DELAWARE**

**GMB FILE NO. 140202**

**General Note:** The following supplementary data and corrective notations are hereby made a part of this project. The General Contractor is responsible for notifying his suppliers and subcontractors regarding items covered by all addenda.

**Contractor Questions**

Below are questions received through 5:00PM, July 22, 2015; wording of some questions may have been modified to suit format of this document.

1. What is the PC / SCADA HMI Software used at the WWTP?

*The software is Iconics.*

2. Will the Contractor use the Owner's development software or will the Contractor need to furnish a new one?

*The Owner owns the development software needed to complete programming work. The HMI at the station will be Magelis, programmed by the Contractor with Vijeo, Version 6.1 Software. The PLC at the station will be Modicon M340, programmed by the Contractor with Unity Software.*

3. May the concrete top slab be constructed as two (2) precast concrete tops?

*Top slab shall be cast-in-place construction as shown on the Contract Drawings.*

**PLEASE ACKNOWLEDGE THIS ADDENDUM ON PAGE 00300-1 OF YOUR BID FORM.  
FAILURE TO ACKNOWLEDGE ALL ADDENDA COULD RESULT IN  
REJECTION OF YOUR BID.**

**\*\*\*END OF ADDENDUM NO. 2\*\*\***